



ADDENDUM

Invitation-To-Bid

Church and Lovejoy Sidewalks LMIG 2022

Date of Addendum Issuance: November 10th, 2022

Addendum Nos.: #2

Addendum Description:

- Replace page 31 – Exhibit B (Specifications & Scope of Work) with the corrected Exhibit as attached.
- Replace page 54 – Exhibit J (Bid Schedule) with the corrected Exhibit as attached.

EXHIBIT B

SPECIFICATIONS AND SCOPE OF WORK**Contract Duration:**

120 calendar days

Project Limits:

Church Street sidewalk construction from the end of the existing sidewalk at the Mell Ave Trailhead Park to Lovejoy Street and Lovejoy Street from the Church Street intersection to the PATH trail – approximately 600 feet.

Project Description:

The Church and Lovejoy Street sidewalk project scope includes 4-5 ft. sidewalk construction and use of pervious rubberized asphalt at specific locations (at specimen tree root zones), a 12-18 inch 18 inch grass “beauty strip”, catch basin reconstruction, resetting existing granite curb, driveway reconstruction, pedestrian ramps, streetscape furniture installation, mailbox resetting or replacement, new retaining wall, handrail and a CMU wall reconstruction. No utility relocations are anticipated.

Scope

The contractor shall furnish all materials, equipment, and labor to complete the required construction as described in its entirety to the Project Plans and Specifications and the terms of this contract including all incidentals as directed by the Project Engineer for the City of Clarkston Unless otherwise specified all work shall be completed in accordance with Georgia Department of Transportation Standard Specifications (current edition), by a completion date.

The selected contractor shall also be responsible funding the cost of all material testing associated with this project. The selected materials testing firm must be GDOT pre-qualified. Testing frequency shall be no less than 1 set of 3 cylinders per 50 CY of concrete per day for all retaining wall and sidewalk work tasks.

EXHIBIT J
BID SCHEDULE

City of Clarkston, GA

2022 LMIG CHURCH ST. AND LOVEJOY ST. SIDEWALKS

Project Description: Provide all labor, materials, equipment and services for grading, demolition, new sidewalk, crosswalks, ADA ramps, streetscape furniture, trees, driveway reconstruction and related tasks

Item Code	Item Description	Qty	Unit Item	Unit Price	Cost
150-1000	TRAFFIC CONTROL	1	LS		
163-0232	TEMPORARY GRASSING	0.2	AC		
165-0010	MAINTENANCE OF TEMPORARY SILT FENCE; TYPE A	600	LF		
171-0010	TEMPORARY SILT FENCE; TYPE A	600	LF		
210-0100	GRADING COMPLETE ¹	1	LS		
430-0160	PLAIN PC CONC PVMT, CL 1 CONC, 6 INCH THICK	10	SY		
441-0018	DRIVEWAY CONCRETE, 8 IN TK W/ FIBER MESH	50	SY		
441-0104	CONC. SIDEWALK, 4 IN	340	SY		
441-6012	CONC CURB & GUTTER, 8 IN X 24 IN	200	LF		
441-7011	CURB CUT WHEELCHAIR RAMP. TYPE A (includes detectable warning surface truncated domes – yellow)	3	EA		
441-7011	CURB CUT WHEELCHAIR RAMP, TYPE D (includes detectable warning surface truncated dome - yellow)	8	EA		
500-3201	GDOT RETAINING WALL; CLASS B	15	CY		
500-9999	CLASS B CONC. BASE (for granite curb reset)	50	CY		
611-5280	RESET GRANITE CURB	350	LF		
643-8200	BARRIER FENCE (ORANGE), 4 FT. TREE PROTECTION FENCE	100	LF		
653-1804	THERMO SOLID TRAF STRIPE 8 IN CROSSWALK, WHITE	300	LF		
668-1100	CATCH BASIN, GP 1 (includes brick riser)	1	EA		
NA	LANDSCAPE ³	1	LS		
700-9300	SOD (Bermuda - Tifway 419)	200	SY		
702-0030	ACER RUBRUM – OCTOBER FLORY RED MAPLE – 3" DBH ²	4	EA		
702-9025	LANDSCAPE MULCH (black)	50	SY		
754-4000	WASTE RECEPTACLE UNIT ⁴	1	EA		
754-5000	BENCH (4 ft.) ⁴	1	EA		
NA	POROUS RUBBERIZED SIDEWALK 6 IN.. ⁵	50	SY		
643-8300	ORNAMENTAL FENCE (black)	10	LF		
NA	OWNER CONTINGENCY	1	LS	5.000	5.000
TOTAL					\$

- Note:** (1) Includes grading for sidewalks, reset mailboxes, demolition of existing walls and driveways including disposal costs
(2) Tree Installations; 1 year warranty for tree replacements – warranty commence when punch list is accepted by the City. Includes 18 feet of root barrier and nursery planting soil – 2 CY
(3) Mulch for trees
(4) Refer to the plan specifications on the Site Plan; submittal to city required – Exhibit O. Location TBD by city
(5) Refer to Exhibit P – submittal to city required. Shall be placed within are the direction of the inspector