



## **ADDENDUM**

### **Invitation-To-Bid**

#### **Church and Lovejoy Sidewalks LMIG 2022**

**Date of Addendum Issuance:** November 10, 2022

**Addendum Nos.:** #3

**Addendum Description:**

- Replace page 54 – Exhibit J (Bid Schedule) with the corrected Exhibit as attached.

**EXHIBIT J**  
**BID SCHEDULE**

**City of Clarkston, GA**

**2022 LMIG CHURCH ST. AND LOVEJOY ST. SIDEWALKS**

**Project Description:** Provide all labor, materials, equipment and services for grading, demolition, new sidewalk, crosswalks, ADA ramps, streetscape furniture, trees, driveway reconstruction and related tasks

| Item Code    | Item Description  | Qty | Unit Item | Unit Price | Cost      |
|--------------|---|-----|-----------|------------|-----------|
| 150-1000     | TRAFFIC CONTROL   | 1   | LS        |            |           |
| 163-0232     | TEMPORARY GRASSING  | 0.2 | AC        |            |           |
| 165-0010     | MAINTENANCE OF TEMPORARY SILT FENCE; TYPE A   | 600 | LF        |            |           |
| 171-0010     | TEMPORARY SILT FENCE; TYPE A  | 600 | LF        |            |           |
| 210-0100     | GRADING COMPLETE <sup>1</sup>   | 1   | LS        |            |           |
| 430-0160     | PLAIN PC CONC PVMT, CL 1 CONC, 6 INCH THICK   | 10  | SY        |            |           |
| 441-0018     | DRIVEWAY CONCRETE, 8 IN TK W/ FIBER MESH  | 50  | SY        |            |           |
| 441-0104     | CONC. SIDEWALK, 4 IN  | 340 | SY        |            |           |
| 441-6012     | CONC CURB & GUTTER, 8 IN X 24 IN  | 200 | LF        |            |           |
| 441-7011     | CURB CUT WHEELCHAIR RAMP. TYPE A (includes detectable warning surface truncated domes – yellow) | 3   | EA        |            |           |
| 441-7011     | CURB CUT WHEELCHAIR RAMP, TYPE D (includes detectable warning surface truncated dome - yellow)  | 8   | EA        |            |           |
| 500-3201     | GDOT RETAINING WALL; CLASS B  | 15  | CY        |            |           |
| 500-9999     | CLASS B CONC. BASE (for granite curb reset)   | 50  | CY        |            |           |
| 611-5280     | RESET GRANITE CURB  | 350 | LF        |            |           |
| 643-8200     | BARRIER FENCE (ORANGE), 4 FT. TREE PROTECTION FENCE   | 100 | LF        |            |           |
| 653-1804     | THERMO SOLID TRAF STRIPE 8 IN CROSSWALK, WHITE  | 300 | LF        |            |           |
| 668-1100     | CATCH BASIN, GP 1 (includes brick riser)  | 1   | EA        |            |           |
| NA           | LANDSCAPE <sup>3</sup>  | 1   | LS        |            |           |
| 700-9300     | SOD (Bermuda - Tifway 419)  | 200 | SY        |            |           |
| 702-0030     | ACER RUBRUM – OCTOBER FLORY RED MAPLE – 3” DBH <sup>2</sup>                                     | 4   | EA        |            |           |
| 754-4000     | WASTE RECEPTACLE UNIT <sup>4</sup>  | 1   | EA        |            |           |
| 754-5000     | BENCH (4 ft.) <sup>4</sup>  | 1   | EA        |            |           |
| NA           | POROUS RUBBERIZED SIDEWALK 6 IN. <sup>5</sup>   | 50  | SY        |            |           |
| 643-8300     | ORNAMENTAL FENCE (black)  | 10  | LF        |            |           |
| NA           | OWNER CONTINGENCY   | 1   | LS        | 5,000      | 5,000     |
| <b>TOTAL</b> |   |     |           |            | <b>\$</b> |

- Note:** (1) Includes grading for sidewalks, reset mailboxes, demolition of existing walls and driveways including disposal costs  
(2) Tree Installations; 1 year warranty for tree replacements – warranty commence when punch list is accepted by the City. Includes 18 feet of root barrier and nursery planting soil – 2 CY  
(3) Mulch for trees. Assume 6 bales of pine straw  
(4) Refer to the plan specifications on the Site Plan; submittal to city required – Exhibit O. Location TBD by city  
(5) Refer to Exhibit P – submittal to city required. Shall be placed within are the direction of the inspector