



**SPLOST 04D**

**EAST PONCE DE LEON & CHURCH STREET PEDESTRIAN  
IMPROVEMENTS**

**ADDENDUM**

(11 pages)

**Date of Addendum Issuance:** March 18<sup>th</sup>, 2019

**Addendum No.:** 3

**Description of Addendum:**

The following Revised Schedule of Bid Items, dated 3/19/2019, shall replace the Schedule of Bid Items in the ITB dated February 25<sup>th</sup>, 2019:

**(BIDDERS MUST RETURN THIS FORM WITH BID RESPONSE)**

**EXHIBIT A**

3/19.2019

**BID SCHEDULE OF ITEMS** (10 pages)

**Contract Scope:** Phase I work required under the Contract includes furnishing all labor, materials, and equipment for the demolition, grading, and sidewalk, granite header curb, landscape and pedestrian ramp installation, striping, Rapid Rectangular Flashing Beacons (2) and signal mast arm poles and related work tasks. Phase II work, upon City receiving CSX permit, will include furnishing all labor, materials, and equipment for grading, demolition, sidewalks, granite header curb, stormwater culverts, decorative fencing, striping and related tasks

**City of Clarkston; DeKalb County  
SPLOST 4D - PONCE DE LEON AND CHURCH ST PEDESTRIAN IMPROVEMENTS**

<b>ITEM CODE</b>	<b>ITEM DESCRIPTION</b>	<b>QTY</b>	<b>UM</b>	<b>UNIT PRICE</b>	<b>COST</b>
<b>BASE BID (A) - ALL WORK OUTSIDE CSX ROW – PHASE I</b>					
150-1000	TRAFFIC CONTROL	1	LS		
151-1000	MOBILIZATION	1	LS		
163-0232	TEMPORARY GRASSING	.28	AC		
163-0240	MULCH	.56	TN		
163-0550	CONSTRUCT AND REMOVE INLET SEDIMENT TRAP	9	EA		
165-0030	MAINTENANCE OF TEMPORARY SILT FENCE, TP C	2,204	LF		
165-0105	MAINTENANCE OF INLET SEDIMENT TRAP	9	EA		
171-0030	TEMPORARY SILT FENCE; TYPE C	2,204	LF		
210-0100	GRADING COMPLETE	1	LS		

310-5060	GR AGGR BASE CRS, 6 INCH, INCL MATL	141	SY		
402-1802	RECYCLED ASPH CONC PATCHING, INCL BITUM MATL & H LIME	22	TN		
402-3103	9.5 MM SUPERPAVE	15.47	TN		
402-3121	25 MM SUPERPAVE	46.13	TN		
402-3190	19 MM SUPERPAVE	23.27	TN		
413-0750	TACK COAT	17	GAL		
437-1571	STRAIGHT GRANITE CURB, 5 IN X 17 IN, TP A	2146	LF		
437-2571	CIRCULAR GRANITE CURB, 5 IN X 17 IN, TP A	230	LF		
441-0104	CONC SIDEWALK, 4 IN	478	SY		
441-0748	CONCRETE MEDIAN, 6 IN	106	SY		
441-7011	CURB CUT WHEELCHAIR RAMP, TYPE A	2	EA		
441-7012	CURB CUT WHEELCHAIR RAMP, TYPE B	2	EA		
441-7014	CURB CUT WHEELCHAIR RAMP, TYPE D	5	EA		
444-1000	SAWED JOINTS IN EXIST PAVEMENTS - PCC	210	LF		
500-9999	CLASS B CONC, BASE OR PVMT WIDENING	98	CY		
550-1150	STORM DRAIN PIPE, 15 IN, H 1-10	71	LF		
607-4100	STONE SEAT WALL	300	SF		

610-0400	REM CONC HDR CURB ALL SIZES	320	LF		
610-0714	REM CONC MEDIAN	470	SY		
610-1005	REM GRANITE CURB ALL SIZES	1756	LF		
610-2815	REM CONC SIDEWALK	239	SY		
610-6515	REM HIGHWAY SIGN, STD	4	EA		
611-3010	RECONSTR DROP INLET, GROUP 1	2	EA		
611-5360	RESET HIGH SIGN	4	EA		
611-8040	ADJUST DROP INLET TO GRADE	2	EA		
611-8050	ADJUST MANHOLE TO GRADE	3	EA		
611-8140	ADJUST WATER VALVE BOX TO GRADE	2	EA		
615-1100	DIRECTIONAL BORE PIPE – 5 IN.	235	LF		
636-1036	HIGHWAY SIGNS, TP 1 MATL, REFL SHEETING, TP 11	45	SF		
636-1041	HIGHWAY SIGNS, TP 1 MATL, REFL SHEETING, TP 9	170	SF		
636-2070	GALV STEEL POSTS, TP 7	251	LF		
639-3004	STEEL STRAIN POLE, TP IV (W/35 FT MAST ARM)	1	EA		
639-3004	STEEL STRAIN POLE, TP IV (W/65 FT MAST ARM & W/45 FT MAST ARM)	1	EA		
647-1000	TRAFFIC SIGNAL INSTALLATION NO. 1	1	LS		

647-3000	INTERNALLY ILLUMINATED STREET SIGN	3	EA		
647-3100	INTERNALLY ILLUMINATED STREET SIGN CONTROL ASSEMBLY	1	EA		
652-9001	TRAFFIC STRIPE, WHITE	102	SY		
652-9002	TRAFFIC STRIPE, YELLOW	317	SY		
653-0120	THERMOPLASTIC PVMT MARKING, ARROW, TP 2	4	EA		
653-0130	THERMOPLASTIC PVMT MARKING, ARROW, TP 3	1	EA		
653-1501	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, WHITE	255	LF		
653-1502	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, YELLOW	3785	LF		
653-1704	THERMOPLASTIC SOLID TRAF STRIPE, 24 IN, WHITE	115	LF		
653-1804	THERMOPLASTIC SOLID TRAF STRIPE, 8 IN, WHITE	1810	LF		
653-3501	THERMOPLASTIC SKIP TRAF STRIPE, 5 IN, WHITE	97	LF		
653-3502	THERMOPLASTIC SKIP TRAF STRIPE, 5 IN, YELLOW	27	GLF		
654-1001	RAISED PVMT MARKERS TP 1 (YELLOW)	350	EA		
654-1003	RAISED PVMT MARKERS TP 3 (RED/CLEAR)	6	EA		
668-2100	DROP INLET, GP 1	3	EA		
682-6233	CONDUIT, NONMETAL, TP 3, 2 IN	1730	LF		
700-8910	PERMANENT GRASSING	.89	AC		

700-9300	SOD - ZOYSIA X 'ZEON'	361	SY		
701-9999	WILDFLOWER SEEDING - ROUNDSTONE SEED MIX 199	331	SY		
702-0001	CHASMANTHIUM LATIFOLIUM	9	EA		
702-0002	DESCHAMPSIA CESPITOSA 'GOLDTAU'	899	EA		
702-0165	CLETHRA ALNIFOLIA	12	EA		
702-0269	FESTUCA GLAUCA 'BEYOND BLUE'	279	EA		
702-0479	ITEA VIRGINICA	14	EA		
702-0528	LAGERSTROEMIA INDICA HYBRIDS	6	EA		
702-0679	MUHLENBERGIA CAPILLARIS 'WHITE CLOUD'	14	EA		
702-9025	LANDSCAPE MULCH	1,233	SY		
708-1000	PLANT TOPSOIL	250	CY		
999-3800	RECTANGULAR RAPID BEACON ASSEMBLY INSTALLATION NO. 1	1	LS		
999-3800	RECTANGULAR RAPID BEACON ASSEMBLY INSTALLATION NO. 2	1	LS		
999-3800	RECTANGULAR RAPID BEACON ASSEMBLY INSTALLATION NO. 3	1	LS		
999-3900	TESTING - RECTANGULAR RAPID BEACON ASSEMBLY	3	EA		
999-3975	TRAINING - RECTANGULAR RAPID BEACON ASSEMBLY	3	EA		
999-3975	DETECTABLE WARNING SURFACE	185	SF		

NA	CONC 18" GUTTER TRANSITION	12	SF		
NA	COORDINATE WITH MARTA; BUS SHELTER RELOCATION BY OTHERS	1	LS		
NA	PAYMENT & PERFORMANCE BOND (cost to purchase)	1	LS		
				<b>TOTAL BASE BID (A)</b>	<b>\$</b>

**ADD ALTERNATE (B) - ALL WORK INSIDE CSX ROW – PHASE II  
(ANTICIPATE AUTUMN 2019 LET)**

150-1000	TRAFFIC CONTROL	1	LS		
151-1000	RE-MOBILIZATION	1	LS		
163-0222	TEMPORARY GRASSING	1.19	AC		
163-0240	MULCH	2.38	TN		
163-0550	CONSTRUCT AND REMOVE INLET SEDIMENT TRAP	3	EA		
165-0030	MAINTENANCE OF TEMPORARY SILT FENCE, TP C	4,816	LF		
165-0105	MAINTENANCE OF INLET SEDIMENT TRAP	3	EA		
167-1000	WATER QUALITY MONITORING & SAMPLING	1	EA		
171-0030	TEMPORARY SILT FENCE, TYPE C	4,816	LF		
210-0100	GRADING COMPLETE	1	LS		
402-3103	9.5 MM SUPERPAVE (FOR PATCHING AT RR XING)	10.7	TN		

402-3121	25 MM SUPERPAVE	16.2	TN		
402-3190	19 MM SUPERPAVE	8.1	TN		
413-0750	TACK COAT	6	GAL		
441-0104	CONC SIDEWALK, 4 IN	1532	SY		
441-4040	CONC VALLEY GUTTER WITH CURB, 6 IN	27	SY		
441-5002	CONCRETE HEADER CURB, 6 IN	32	LF		
441-7011	CURB CUT WHEELCHAIR RAMP, TYPE A	5	EA		
441-7012	CURB CUT WHEELCHAIR RAMP, TYPE B	1	EA		
441-7014	CURB CUT WHEELCHAIR RAMP, TYPE D	1	EA		
500-3800	CLASS A CONCRETE, INCL REINF STEEL (HEADWALLS)	5	CY		
550-1150	STORM DRAIN PIPE, 15 IN, H 1-10 (HDPE)	47	LF		
550-1240	STORM DRAIN PIPE, 24 IN, H 1-10 (RCP)	42	LF		
550-1300	STORM DRAIN PIPE, 30 IN, H 1-10 (HDPE)	430	LF		
550-4215	FLARED END SECTION 15 IN, STORM DRAIN	1	EA		
603-2012	STN DROPPED RIP RAP, TP 1, 12 IN	90	SY		
611-3000	RECONSTR CATCH BASIN, GROUP 1	2	EA		
641-1100	GUARDRAIL, TP T (UTILITY POLE AT 107+00)	8	LF		
643-8300	ORNAMENTAL FENCE	1,517	LF		



668-2100	DROP INLET, GP 1	2	EA		
700-6910	PERMANENT GRASSING	.89	AC		
700-9300	SOD - ZOYSIA X 'ZEON'	1,069	SY		
701-9999	WILDFLOWER SEEDING - ROUNDSTONE SEED MIX 199	1,683	SY		
702-0001	CHASMANTHIUM LATIFOLIUM	42	EA		
702-0043	AESCLUSUS PARVIFLORA	20	EA		
702-0106	CALLICARPA AMERICANA	30	EA		
702-0165	CLETHRA ALNIFOLIA	22	EA		
702-0478	ILLICIAM PARVIFLORUM	23	EA		
702-0479	ITEA VIRGINICA	44	EA		
702-0528	LAGERSTROEMIA X 'BILOXI'	6	EA		
702-0679	MUHLENBERGIA CAPILLARIS 'WHITE CLOUD'	355	EA		
702-9025	LANDSCAPE MULCH	519	SY		
999-5200	DETECTABLE WARNING SURFACE	73	SF		
NA	CONC 18" GUTTER TRANSITION	8	SF		
NA	COST TO ACQUIRE CERTIFICATE OF INSURANCE FOR WORK WITHIN CSX ROW	1	LS		
NA	PAYMENT & PERFORMANCE BOND (cost to purchase)	1	LS		
NA	COORD WITH CONCRETE PANEL RAILROAD CROSSING INSTALLATION BY OTHERS (CSXT)	1	LS		

<b>TOTAL BID ADD ALT. (B)</b>	<b>\$</b>
---	-----------

**ADDITIONAL ITEMS (C) IF ORDERED BY THE ENGINEER**

	REMOVAL OF UNSUITABLE MATERIAL AND REPLACEMENT WITH SUITABLE EARTH MATERIAL	50	CY		
	REMOVAL OF UNSUITABLE MATERIAL AND REPLACEMENT WITH GRADED AGGREGATE BASE	50	CY		
310-1101	GR AGGR BASE CRS, INCL MATL	10	TN		
636-3600	REMOVE EXISTING TRAF STRIPING, ALL KINDS & TYPES	20	SY		
				<b>TOTAL BID ADDITIONAL ITEMS (C)</b>	<b>\$</b>

=====  
**Print Total Bid Price for "A": (print)** \_\_\_\_\_

**Print Total Bid Price for "B": (print)** \_\_\_\_\_

**Print Total Bid Price for "C": (print)** \_\_\_\_\_

=====

**TOTAL BID FOR "A", "B" & "C":**      \$ \_\_\_\_\_

**TOTAL BID FOR "A", "B" & "C" (print)** \_\_\_\_\_

=====

**\*\*\*\*\* Bidders are required to submit bids for "A", "B" & "C" \*\*\*\*\***

The City, at a minimum, will select a contractor for the **BASE BID**. The City reserves the right to award a contract for Bids “B” and/or “C” at its discretion. If the city awards a contract for Bids “B” and/or “C”, the decision for award will be based on the SUMMATION OF ALL THREE BID AMOUNTS.

**\*\*\*\*\* The City decision for a Bid Award  
will be based on the summation of all three (3) Bids \*\*\*\*\***

In compliance with the attached Specification, the undersigned offers and agrees that if this Bid is accepted by the CITY, that he will furnish any or all of the Items upon which Prices are quoted, at the Price set opposite each Item, delivered to the designated point(s) and that the submitted bid will be valid from the date of the contract signature by both parties to the date of the city’s NTP issuance (duration not to exceed 60 days) and said submitted bid price shall remain valid during the entire duration of the construction.

COMPANY \_\_\_\_\_

ADDRESS \_\_\_\_\_

AUTHORIZED SIGNATURE \_\_\_\_\_

PRINT / TYPE NAME \_\_\_\_\_

TITLE \_\_\_\_\_